## COMPONENT CODE A1

PARTS & SERVICE	F
NEWS	Ι
	(

REF NO.	AT04050
DATE	Mar. 26, 2004
$(\mathbf{C})$	Page 1 of 2

- **SUBJECT:** IMPROVED SEAL FOR ENGINE CYLINDER HEAD COVER ON SAA6D114E-2
- **PURPOSE:** To introduce an improved engine cylinder head cover seal for the SAA6D114E-2 engines

APPLICATION:SAA6D114E-2 (All machines)PC300LC-7Hydraulic ExavatorsSerial Nos. 40001 and upWA380-5Wheel LoadersSerial Nos. 60001 and upGD655-3Motor GradersSerial Nos. 1001 and upGD675-3Motor GraderSerial Nos. 110(1 ard upCD110R-2Crawler Dump TrucksSerial Nos. 1501 and up


## FAILURE CODE: A1B0AA

## **DESCRIPTION:**


- 1. Introduction This Service News will introduce an improved up ne cylinder head cover seal (O-ring) for the SAA6D114E-2 engines.
- 2. List of parts

Part No.	Part N.me	Q'ty	Remarks
6741-11-8121 (6741-11-8120)	Seal	1	Head cover O-ring
(6741-11-8120) 6741-11-8180 (6732-11-81.0)	(Sear) Washer (Washer)	(1) $(6)$	Cover mounting washers

3. Details of the improvement



(1) Improvement of the seal (O-ring) In order to increase the bearing factor at the front and that ends, the thickness of the O-rings used at the ends has been increased.



(2) Improvement of the washer In order to increase the overall bearing factor, <u>the thickness of the cover mounting</u> <u>washers</u> as been increased.




Fig. 3

4. Replacement procedure The replacement procedure for the improved parts is the same as the replacement procedure for the current parts. (Refer to the Chapter "Disassembly and Assembly" in the Shop Manual.